

February 20, 2026

Addendum No. 1

BL037-26

M1080.71 Gwinnett County Traffic Signal Upgrades (10 Locations)

FOR THE CONTRACTORS' INFORMATION:

- Q1.** I noticed that there is a tree called out for removal, which pay item will it be paid out on.
- R1.** Grading Complete
- Q2.** There is a call out for a cutout for the concrete median, will this be paid out under grading complete, or does it have its own item.
- R2.** Any grading or demo work – Grading Complete, any concrete work would be paid under the appropriate concrete pay item listed in the bid schedule.
- Q3.** What is the 750 cy of undercut excavation pertaining to? I don't see it shown on the plans anywhere and wanted to know what kind of work was being done.
- R3.** This is to be used as directed by the engineer in accordance with section 210 of the GDOT Specifications.
- Q4.** Will 18-gauge, 3 pair be acceptable for pushbuttons and loops or will 14-gauge, 3 pair be required? Or will it be 3-conductor 20 AWG stranded cable (3M model 138)?
- R4.** APS requires 14-gauge, 3-pair for installation. There are not any loops on this project.
- Q5.** Will E-Locks be acceptable to connect HDPE conduit or will compression couplings be required?
- R5.** Compression couplings are required.
- Q6.** Can the contract time be adjusted based on the issuance of an NTP rather than a hard date of March 31, 2027?
- R6.** No, March 31, 2027, is a hard deadline.
- Q7.** Which size/insulation type tracer wire is required for fiber installations?
- R7.** 10 gauge
- Q8.** For ped pole foundations, will concrete foundations be allowed? The note below references screw-in type foundations for the ped poles. If screw-in type foundations are required, what length/depth shall they be?
- 1.2.7 Pedestal pole foundations are preformed steel streetlight foundations that are directly screwed into the ground by auger truck without excavation. (Chance C11232JG4VL)
- R8.** Concrete foundations are allowed. Precast foundations are not allowed.

ADDENDUM #1

Q9. Will the County add an add-alternate pay item for rock removal?

R9. No

Q10. If pay item will not be added, will a change order be allowed if rock is encountered?

R10. No

Q11. Can you provide the alignment data for the referenced project. Just to clarify, the minimal information needed would be at least the start and end coordinate labels to be provided since they are missing in the plans.

R11. Information not available.

Q11. Can the County provide a bid tabulation for a similar project?

R11. The County is unable to provide a bid tabulation for a similar project, as this project's scope is unique and no comparable project is available.

If wanting a copy of the bid tabulation for the County's Annual Contract titled BL132-25 Traffic Signal and Intelligent Transportation System (ITS) Demand Services, please submit an open records request through the Gwinnett County website.

You should acknowledge receipt on Page I-4 of the bidding documents.

FAILURE TO ACKNOWLEDGE THE ADDENDUM MAY RESULT IN REJECTION OF YOUR BID.

RECEIPT OF BIDS REMAINS UNCHANGED: 2:50 PM LOCAL TIME, THURSDAY, FEBRUARY 26, 2026.