

**40 91 01
ADDENDUM NUMBER 01**

Owner: Gwinnett County Board of Commissioners

Project: BL039-26, Eva Kennedy Road Water Main Replacement

Project No.: M00736.67

Addendum No. 01

Addendum Date: 4/15/2026

The following additions, deletions, modifications, or clarifications shall be made to the appropriate portions of the Contract Documents. Bidders must acknowledge receipt of this Addendum in the space provided on the Bid Form.

Approved by: <u>Tetra Tech</u>
Name: <u>Vineeth Sasidhara Panicker</u>
Date: <u>04/14/2026</u>
 <p>Tetra Tech Georgia Registered Engineering Firm, K909924</p>
Addendum Items:
Article 1– Addendum <i>Section 1.01-1.02</i> Article 3 – Specifications <i>Section 3.01</i> Article 6 – Questions <i>Section 6.01-6.06</i>

ARTICLE 1 – ADDENDUM

1.01 Amend the Contract Documents

- A. Make the additions, modifications, or deletions to the Contract Documents described in this Addendum.

1.02 Acknowledge Addenda

- A. Acknowledge receipt of this Addendum in the Bid Form submitted for this Project. Failure to acknowledge receipt of this addendum in the Bid Form may render the Bid as non-responsive and serve as the basis for rejecting the Bid.

ARTICLE 2 – BID REQUIREMENTS

No updates in Addendum 1.

ARTICLE 3 – SPECIFICATION

3.01 32 12 16 Asphalt Paving

- A. Paragraph 1.5, A., Page 32 12 16-2
 - 1. Clarification: Contractor shall provide Warranty for all paving and pavement related work (including base repair, asphalt, and pavement restoration within the roadway) for a period of eighteen (18) months from the date of Substantial Completion.

ARTICLE 4 – DRAWINGS

No updates in Addendum 1.

ARTICLE 5 – APPENDICES

No updates in Addendum 1.

ARTICLE 6 – QUESTIONS

6.01 Please provide sizes for the service connections. Are these all ¾"? Will the long side services need 2" PVC casing?

- A. Residential connections are typically ¾" (minimum size). The contractor should verify the existing water meter size and match service connections to meet the meter size. Long side service connections are installed via trenchless method across the road and do not require 2" PVC casing.

6.02 Is the cast-in-place concrete strictly for the trench cap? Concrete for thrust blocking to be in water main items?

- A. No, not strictly. Trench cap concrete costs should be included in cast-in-place concrete (M&P Item 4). There could be other cast-in-place concrete that is needed but not identified. Thrust restraint, thrust block concrete, and bedding should be included with DIP Water Main Items (M&P Item 29).

- 6.03 Are portable signs allowed for this project?
- A. Yes, Portable signs are allowed, and the cost is to be included in Traffic Control Devices (M&P Item 43)
- 6.04 Please confirm that the thrust restraints, concrete, and bedding are included in the pipe price under Measurement Line Item 29.
- A. Thrust restraints, concrete, and bedding costs should be included with DIP Water Main Items (M&P Item 29) per specification section 01 29 01 Measurement and Basis for Payment.
- 6.05 Please confirm whether the concrete cap is also to be included in the pipe price, or if it should be accounted for as a separate line item.
- A. Trench cap concrete cost is to be included in cast-in-place concrete (M&P item 4) per specification section 01 29 01 Measurement and Basis for Payment.
- 6.06 Please provide the bid documents for this project.
- A. Bid documents can be requested from Ashley.Campbell@TetraTech.com per the Notice to Bid.

END OF ADDENDUM NO. 01